3. The sale is subject to the confirmation of the Superintendent, Government Gardens in Mysore, and the articles shall be delivered only when the sale is so confirmed.

4. The machines are kept in the office of the undersigned for inspection during office hours between 11 A.M. and 5 P.M. Any complaint received thereafter about the condition of the machines will not be entertained.

5. In the event of any dispute, the decision of the Superintendent, Government Gardens in Mysore, is final and legally binding.

L. S. DORASAMI,
Superintendent.

GOVERNMENT OF MYSORE—ELECTRICAL DEPARTMENT.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, BHADRAVATI.

1. Sealed tenders in triplicate will be received at the Office of the Superintendent, Power and Lighting, Bhadravati, superscribed with the name of the work mentioned below.

2. The plans connected with the work may be seen at the Office of the undersigned and Office of the Senior Operator, Power and Light, Shimoga, at all working hours. The copy, if required, will be made available on payment of Rs. 5 per set.

3. The tenders should be drawn up strictly in conformity with the specifications furnished, writing out the rates at which each item of work will be executed in figures as well as in words, failing which no cognisance will be taken of the tender. No items other than those noted in the statement should be included as the items cover provision for all sundries, repairs to damaged masonry and painting.

4. The materials to be used on the work should be of best quality conforming to the specification of this department and B. S. or A. I. E. E. specifications. Mention should also be made of the manufacture and the catalogue number of the materials offered. Teakwood planks to be used on the work should be free from knots, cracks and well seasoned. No planks less than 12″ in width will be permitted to be used unless it is to make up the difference in size of the board required. Only the lap joints should be adopted in all cases. Lamp holders, ceiling roses, control switches, covers, etc., should be of reinforced bakelite material.

5. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

6. The successful tenderer will be required to deposit an earnest money of Rs. 60 (Rupees sixty only) and execute an agreement within a week from the date of intimation of acceptance of the tender. He should send samples of all the materials required for the work mounted on a board and start the work after obtaining the approval of the undersigned with regard to the same and carry out the wiring following the rules of this department as well as that of the Institution of Electrical Engineers. He should also be prepared to adopt any change in the location of control points and other outlets that might be suggested by the undersigned during the progress of the work without extra cost if the tender is not materially affected by such deviations.

7. The undersigned reserves the right also to reject the work either in full or in part if he finds the work not carried out in terms of the specifications or is otherwise dissatisfied with the workmanship.

8. *Name of work.*—"Installing Electric Lights to the Railway Station at Shimoga."

9. *Last date for receiving tenders.*—3rd January 1939.

10. *Date and time of opening the tenders in public.*—3rd January 1939 at 3 P.M.

11. A period of three weeks will be allowed for final completion of the work with effect from the date of final acceptance of the tender. A penalty of Rs. 10 (Rupees ten) for each day's delay over and above the stipulated period during the first week and Rs. 20 (Rupees twenty) during the second week will be imposed. If there be further delay the department will take charge of the installation at whatever stage it might be and arrange for its completion through any other agency entirely at the risk of the tenderer.

12. It will be obligatory on the part of the tenderer executing the work to attend to any major troubles that might crop up due to bad workmanship, etc., during the first twelve months from the date of handing over the installation to this department without any return for services rendered.

13. *Details of work.*—The quantities given in the annexed statement are not guaranteed and are subject to variation at the time of executing the work.

DETAILS OF WORK.

	Part I—(Exterior).	*Quantity*	
1.	Supplying and fixing S. M. rails 24 feet long and tarring the same	No.	3
2.	Supplying and fixing 2-pin D. C. A. complete and tarring the same	,,	2
3.	Supplying and fixing 2-pin S. C. A. complete and tarring the same	,,	2
4.	Supplying and fixing insulators and pins	,,	12
5.	Supplying and fixing guy sets complete with anchor rod and 7-strand guy wire ..	,,	2
6.	Supplying and stringing bare copper wire No. 8 B. & S.	Ft.	850
		Lbs.	46
7.	Earthing	Lumpsum	
8.	Supplying and running mains in ¾″ W. I. pipe with bends, etc., using No. 12 B. & S., 2,500 meg ohms grade insulated wire and accessories	Ft.	30
	Part I—Total ..		

	Part II—(Interior).	*Quantity*	
1.	Supplying, fixing and wiring a teakwood meter board 24″×24″×1″ with battens and rear board equipping it with one 20 amps. iron-clad switch D. P. S. T. with fuses and one 3-way 10-amp. per way 'Neata' distribution board with 5-amp. bakelite circuit switches using Nos. 8 and 12 B. & S. insulated wire of 2,500 meg ohms grade with accessories	No.	1
2.	Supplying and fixing ornamental lamp post fluted type fitted with ¾″ pipe bracket and "Terrace" fittings with clear glass globe G. E. C. Cat. No. F. 5103-25335, etc., complete for parallel light with 300 watts, B. C. half watt lamp, 220 volts, with 5-amp. tumbler switch and a fuse cutout mounted inside the post with cement concrete foundation complete	No.	4
3.	Supplying and laying underground cable No. 12 B. & S. twin conductor, L. C. J. S., S. C. V. C., insulated for 600 volts pressure for ornamental lamp posts and laying the cable in trench of 3-feet deep and covering the trench with fine river sand 3″ all round and removing surplus earth, etc., and with suitable junction boxes	Feet	500
4.	Miscellaneous materials such as junction boxes, tape, etc., etc.	Lumpsum	
5.	Supplying, fixing and running No. 12 B. & S., 2,500 meg ohms insulated wire in teakwood casing 2″×1″ treated with 2 coats of shellac varnish with 5-amp. bakelite switches, ceiling roses, bow cutouts, 5-amp. B. C. C. G. lamp holders with necessary length of silk cord, opal shades 10″ and 20 to 60 watts, B. C. lamps, 220 volts, complete for drop lights	No.	7
6.	Supplying, fixing and wiring as above for bracket lights with brass bracket 9″, complete	,,	1
7.	Supplying, fixing and wiring pendent lights, complete	,,	3
8.	Supplying, fixing and wiring water-tight fitting, complete	,,	1
	Part II—Total ..		

K. SUBBA RAO,
Superintendent.

THE MYSORE COFFEE CURING WORKS, LIMITED, CHIKMAGALUR.

Tender Notice.

Sealed tenders are invited, so as to reach the undersigned on or before the 20th December 1938, for the construction of the Office and Factory Buildings for the Mysore Coffee Curing Works, Ltd., Chikmagalur.

Specifications and Drawings are available at the Office of the Company at Chikmagalur and can be had during office hours on payment of Rs. 3 per set.

J. Z. SALDANHA,
Manager.

"I, B. Vedantaiengar, B.A. (Hons.), LL.B., intend moving the Honourable the High Court of Mysore to enrol me as an Advocate thereof. B. VEDANTAIENGAR."

Printed by the Superintendent at the Government Press, Bangalore.